# Transportation & Handling of Marley Roof Tiles

### Accessibility

- > Palletised tiles are to be loaded onto the trailer so that they are level and do not protrude and thus cause damages.
- > Loosely loaded fittings on top of a loaded trailer should be neatly stacked as per photograph.
- > Palletised fittings should be shrink-wrapped and secured to wooden pallet.
- > Loosely loaded fitting in ridge boxes on a trailer should be neatly stacked as per photograph.













## Offloading of Roof Tiles

- > Offloading of tiles should be directly next to the trailer. (Do not carry tiles to offloading area)
- > Tiles are to be placed in an upright position with the nail hole at the bottom (Nail hole edge of the tile to ground as per photograph)







We know how important it is to find practical information and to keep up with the latest development in Roofing. Visit our website or scan the QR code for more information on the latest in Roofing news, product and tips.



https://www.facebook.com/MarleyRoofingZA https://www.linkedin.com/company/27058241/

CALL 010 600 0284 FMAII info@marley.co.za OR VISIT www.marleyroofing.co.za

### Let us help you!

If any part of this communication is not clear, please dial our friendly Customer Service Unit for advice and/or clarification



> Tiles are to be stacked to a maximum of three levels.






> Fittings are to be packed and stacked neatly on top of the tiles to a maximum of 15 fittings















#### Site examples

- > A desirable site has enough area for load to be accommodated on firm level ground, which is clear of obstructions (other building material etc.) and out of the way of building vehicles and equipment.
- > An undesirable site's area is not sufficient to cater for load quantity; if the ground is not suitably level, if obstructions from other building materials are present and where equipment hinders vehicle movement.

# Do's & Dont's!



#### 🗭 Don't

